

Tender for Concrete Works.

COMPANY DETAILS

Norwegian Refugee Council

Deadline Date

Mon 4th Apr

E# info@nrc.no

Tender Detail:

Norwegian Refugee Council (NRC) invites bids from competent Construction Companies/ Contractors in Kurdistan for the following works: "Shelter Rehabilitation/ Upgrading of houses inhabited by the IDPs in Shaikhan District, Duhok and Zummar Sub-district of Talafarâ€ -the work is to be undertaken on 225 shelter units; specifications and technical details are as follows.

Closing Date: 04/04/2016

Location: Erbil, Arbil, Iraq

Contact Details: Norwegian Refugee Council Support Office ZRKA 99451, Bangawan Street 52nd st, Dohuk Iraq

Email Address: iq.procurement@nrc.no

Lean floor concrete (124) min thickness 5cm. Building works, (1) Leveling land, back filling and solid block (40*20*15)cm , with cement mortar 13 Masonry, (2) Preparing materials to construct a base for water tank, (3) Providing materials and equipment to install the corrugated plate roof and fixing with possible screw and steel frame (4*4) cm thickness, (4) Providing materials and necessary tools for installing of sandwich panels with 5cm thickness.

Sanitary and Plumbing Works- (1) Provide and install porcelain hand wash basin (45x60 cm), Turkish made with base., (2) Provide and install ceramic eastern toilet base (425x540x210 mm)., (3) Provide and install galvanized water tank (1000 Liters, 1 m

Diameter, 1.25 m Length and 1.2 mm Thickness), (4) Provide and install ¾" plastic water Turkish Made Pipes for internal network and connecting the water supply source to water tank, (5) 4" PVC Pipes Turkish for Water Outlets, with all fixtures and finishing, (6) Provide and install ¾" plastic water tape, Turkish Made., (7) Stainless steel sink (50x120 cm) with two wings and one basin, (8) Septic tank for sewage water, with (2x2x2 m)., (9) Construction of manholes providing materials and constructing (40*40*40) cm concrete or plastic manholes, (10) Construction of toilet, (11) Construction of bathroom, (12) Dislodging septic tank Dislodging existing septic tanks, (13) Open channel Solid block (40x20x15).

Doors & Windows, (!) Provide and install reinforced, Plastic doors PVC., (2) Preparing and installing reinforced, Plastic windows PVC, (3) PVC partitions supplying, transportation, and installation of reinforced PVC Partitions, (4) Steel doors Supplying, transportation, and installation of Steel doors, (5) Windows Glass Installing the new 4 mm glass to the metal frames, (6) Door handles Installing new door handles with locks. (7) Mesh for windows Provide and install mosquito nets over the openable parts of PVC Windows.

Electricity Works, Preparing, Installing, Connecting and Testing Light point. **Finishing works,** (1) Provide the materials and necessary tools for mortar plaster walls., (2) Provide the materials and necessary tools for filling gaps walls.

Disaster Risk Reduction (DRR) Needs, (1) Hand rail Provide and install iron handrail 90cm height., (2) Provide the materials and necessary tools to plug the holes or aperture by using pieces of wood or other materials.

Accessibility inclusion, (1) Rump Providing material and equipment need to build the rumps by solid block (40*20*15)cm. (2) Railing Provide and install iron handrail with circular cross section (2 inch) and the height of 90cm from the stairs floor level., (3) Grip rails Providing materials and installing of steel handles.

Other Works, Provide and install Plastic Sheets (Blue Color) (width=6 m).