

**BoQ RFT N° ADMIN/KIR18/00012 / Khanaqin ICRC Office / Interior walls
paint & PVC partition / Rehabilitation**

Item	Description	Unit	Qty	Unit Price (USD)	Total Price (USD)
1	PVC partition, hole & Painting				
1.1	Providing of materials, manpower and tools (drill hammer) to open new hole (2 x 1)m in the stone wall 40cm thick. The work includes fix the roof of the hole by installing angle iron 3 inches (2 x 2.5 ML) and re-plaster all exposed surfaces , as to instructions of ICRC engineer.	LS	1		
1.2	Supply and install PVC partition (3 x 5)m equipped by sliding door of best type of Turkish made for visitors office. Sections to be of super profile quality, to comply with European standards, profile to be not less than (60)mm total depth, outer wall thickness not less than (3)mm, section to at least (4) chamber, the door sash profile inside and out side laminated with grey joint. panel profile single chambered (100)mm thickness both side laminated. The work also includes making partition one side sewing move to cover the AVR electrical system area size (2m wide x 2m height). Work includes remove the existing pvc partition and door of the upstairs driver unit.	M2	19		
1.3	Supply material, install PVC windows for assistanc, kitchen, com, upstairs, admin, meeting, bathes and visitors rooms, Sections Turkish made to be of super profile (inside & out side laminated) quality comply with European standards, profiles thickness not less than (60)mm total depth, outer wall thickness not less than (3)mm, sections to be at least (4) chamber, total double glazing gap not less than (10)mm. glazing coloured type double of (4x4)mm thick., handles, fibre glass mesh with aluminium frame dimensions (50x100)cm. for opened panels, supplying decorative fringe profile (55x100)mm for internal fringe of the window frames. the price include separate protection steel nets using 12mm square steel bars according to the drawings. with all work requirements & site Engineer direction. remove all metal old window needed and paint the rest.	M2	27		
1.4	Painting all the exposed interior walls, Gypsum plastered walls in three layers using Silicone type painting, best quality .The surfaces should be well cleaned from dirt, dust and oil.	ML	800		
1.5	Providing of materials and technicians and remove the existing wash basin in the entrance with all its plumping. The work includes supply and install new wash basin size (3cm x 30 cm) inside the western W.C with all sewage and pluming connection.	LS	1		

Item	Description	Unit	Qty	Unit Price (USD)	Total Price (USD)
1.6	<p>Fabricating roof bedrooms Sandwich unit: The unit is consist of the following: 1-Two bedrooms, each one size (5.5m x 3.4m) 2-Passage to the rooms and to the stair, size (1.5m x 7m), 3-Covering exterior roof and outskirt walls by metal sheet 3mm thick and Cover it by classic corrugated metal tile (Qarmeed) standard approved sizes. 4-Three pvc windows size (1.5 x 1.75)m. 5-Four pvc doors size (2 x 1)m. 6-Floor ceramic tile approved size & colour for all the sandwich building. 7-Supply and install new exhaust ventilation fan size 40cm Sinar type or best equivalent for the passage. building sandwiches walls over the outskirt fence and roof floor. The compound is made of : metal iron frame base from steel square for the columns size (4x 4)inches for the corners and (2 x 2)inches for the middle top of the rooms, lightweight panel polyurethane foam, steel sheets coloured type of both faces, plastic cover sheet for internal faces, pvc door and windows Turkish made first degree from super profile quality, openings double glazing (4*4)mm thick ; the door switch locked. the floor made of metal frame structure, roof sloped (1%) for rain draining, the walls of sandwiched is made of angle iron size (1.25x1.25)inches, pvc false ceiling reinforced type thermal resist size(60x60)cm, electrical lighting system inside pvc pipe insulation (25)mm diam. the roof metal structure is made of square iron (2 x 4)inches for the outskirt and (2 x 2) inches for the partitions down light steel LED, all fittings with wire conduits, switch lightings & plugs, exhaust fans (8"x8")dimensions. Price includes electrical system installation (MDB, plugs, switches, ect)</p>	Sq.m	56		
1.7	<p>Fabricating Guard and drivers Sandwich Caravan unit and Kitchen unit : the steel structure unit made of square iron columns size (4x4) inches for the corners and (2x4)inches, (1.5x3)inches, for the floor, walls and roof . The floor made of plywood 18mm thick and covered by carpet covering roof by metal sheet 3mm thick and cover it by classic corrugated metal tile (Qarmeed) standard approved sizes. The compound is made of : lightweight panel polyurethane foam, steel sheets coloured type of both faces, plastic cover sheet for internal faces, pvc door and windows Turkish made first degree from super profile quality, openings double glazing (4*4)mm thick ; the door switch locked. roof sloped (1%) for rain draining, the walls of sandwiches is made of angle iron size (1.25x1.25)inches, pvc false ceiling reinforced type thermal resist size(60x60)cm, electrical lighting system inside pvc pipe insulation (25)mm diam. down light steel LED, distribution board & suitable length of power cable, all fittings with wire conduits, switch lightings & plugs, exhaust fans (6"x6")dimensions. Price includes electrical system installation (MDB, plugs, switches, ect) & install the unit over RC concrete rectangular beam size (6.5m x 4m), the cross section of the beam is (40cm x 40 cm)</p>	Sq.	26		
1.8	<p>Supply and install iron main entrance door of the office size (2.5m x 2.1m height), the door should be made of the following: 1-Two parts moving, each part should be size (1.25m x 1.05m). 2-Using angle iron frame (2.5 x 2.5)inches 3-Metal sheet 1.5 mm. 4-Square iron pipe size (1.5 x 1.5)inches. 5-Swich & handle locks.</p>	Sq.m	5.25		
1.81	<p>Supply, install and cover the roof of the existing Shades of (generators (5.5m x 8m + 1.7m x 2m), guard booth (5.6m x 3.5m) and fuel tank (2.35m x 2m) of the residence), the work includes install corrugated metal sheet 1mm thickness three layers over the roof .</p>	Sq.m	72		

Item	Description	Unit	Qty	Unit Price (USD)	Total Price (USD)
1.82	Supply and install plastic cover sheet to cover the area of ceramic walls outside the bathes approved colour and type	Sq.m	12		
1.83	Supply and install LED down 24 watt light to be fixed by pvc rolbolt inside the offices on the roof as an average each room 6 LED to be installed. The work includes all wiring 1.5mm2 inside pcv pipe with switches.	NO	60		
1.84	Supply and install pvc doors size (2m x 2m) to be installed between meeting room and visitors office and size (2m x 1m) for the entrance for the visitors office.	Sq.m	6		
1.85	Supply, Install Split wall-mounted Air Conditioner cool/warm unit, supply and install new outdoor unit with heating and cooling capacity 1.5tons , V220-240, cooling power rated current 15A, maintaining power supply line or plug 40A, DC inverter compressor type, refrigerant piping connection, almost 6m pipe length, wireless remote controller, auto change over. power cable size (2*4 Sq/mm) conduits from MCCB unit B up to switch of out door unit.best equivalent.	NO	5		
1.86	Fence building wall (0.8m higher)m by using clay bricks size (24 x 11.5 x 7.5)cm, approved type. The building is over the existing out-front fence, cement plastering exterior and interior fence. Disconnect the outdoor light on the door, any electrical part and re-install it after finish the work, removing the iron decorative fence and building clay bricks instead, installed it again after finishing the work in the front out side the fence, painting all plastering an iron materials. the building is to fill the spaces as following: 1- (3.5m x 0.8m height). 2- (3.5m x 0.8m height). 3-(3.5m x 0.8m height) 4- (3m x 0.8m height).	ML	11		
1.87	Supply and install plastic cover sheet to cover the area of ceramic skirt 0.3m height inside the office approved colour and type and install decorative end of sheet.	ML	180		
1.88	Clearing the floor mosaic tiles for all the office by using electrical brushes, workers and cleaning materials like (Cleaning Products for Tile Cleaning in the local market).	LS	1		
Grand Total					

Estimated duration	n° of calendar days	
---------------------------	---------------------	--