

FINANCIAL OFFER: washing basin maintenance - Mahmodly camp

العرض المالي: صيانة حوض الغسيل - مخيم المحمودلي

SN	Item description	Unit	Qty	Unit Price (USD)	Total Price (USD)
1	Breaking the washing Basin and removing all debris outside the camp to a place determined by the local authority, the price includes all needed to complete this work(machins, workers, tooles), all the work should be done according to the site engineer instructions.	No	147		
2	Concrete Work: casting concrete washing basin (1:2:4), and the basin as box, Dim of concrete is (55*140*50 cm), and the dim for the empty box (35*120*35 cm), and the thick of sides 10 cm, the price includes install iron sink floor and plastic pipe 4 inches out the basin and all needed to complete this work(workers, tools, materials), all the work should be done according to the site engineer instructions.	No	147		
3	supply and install all materials to extend pipe line by use plastic pipe 4 inches, by excavation channel wide 30 and the deep as manhole needed, the price include connect the pipe to main line- manhole, The Work should be done according to the detail and site engineer instruction	ML	588		
Total Cost (USD)					

NOTES:

- 1- All applicants preferred to visit the site before submitting the offer.
- 2- All the items should be approved by our organization's site engineer.
- 3- The contractor should submit sample of each provided item before installation.
- 4- The contractor should clean the site from all remnant and remaining materials after completing the work to the identified location by local administration.
- 5- Our organization is not bound to buy the whole quantity mentioned in the BOQ.
- 6- Our organization is not bound to contract with one company and can split the award between one or more companies.
- 7- The implementation location is: Mahmoudly Camp NES

ملاحظات:

- 1- يفضل من جميع المتقدمين زيارة الموقع مسبقاً قبل تقديم العرض.
- 2- يجب الموافقة على جميع الفقرات من قبل مهندس الموقع لمنظمتنا.
- 3- يجب على المقاول تقديم عينة من كل مواد مجهزة قبل التثبيت.
- 4- يجب على المقاول تنظيف الموقع من جميع المواد المتبقية والمخلفات المتبقية بعد الانتهاء من العمل ونقله إلى الموقع المحدد من قبل الإدارة المحلية.
- 5- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- 6- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة, و يمكن تجزئة العطاء بين أكثر من شركة
- 7- موقع التنفيذ هو مخيم محمودلي شمال شرق سوريا.

Name of Signatory: _____

Title of Signatory: _____

Name of Bidder: _____

Signature & stamp:

Date of Signing: _____