



Financial Offer: General Maintenance Works in Mahmoodly, Twaihiniyah and Tel Semen Camps - NES

العرض المالي: أعمال الصيانة العامة في مخيمات المحمودلي والطويحينية وتل السمن في شمال شرق سوريا


#	Item Description وصف المادة	Unit الوحدة	QTY الكمية	Photo الصورة	Unit Price (USD) سعر الوحدة بالدولار الامريكي	Total Price (USD) سعر الكلي بالدولار الامريكي
A	Maintenace Work in Tel Al-Samen Camp					
1	Rehabilitation of tents					
1.1	Crushed stone: leveling the site and removal of debris, grading, concrete block with good cleaning , and Supply suitable machine with labore to leveling site, by using equivalent machines, the price includes laying crushed stone best type , the price including watering and compacting the crushed stone, with all necessary needs to complete the work, all the work should be done according to the site engineer instructions.	M³	35			
1.2	Concrete Works;- Supply and cast reinforced concrete (1:2:4) with 15 cm thickness for the floor using BRC mesh (15X15)cm and 6mm thick., the price includes laying thick nylon under the concrete, watering, shuttering, curing and framework by plywood are included as requirements. The concrete surface should be smoothened. with all necessary needs to complete the work, all the work should be done according to the site engineer instructions.	M²	140			
1.3	Supply material hiring staff to re-Installation existed the tent (Dim 10.40*4.6 m + the arc in the roof) in the site by welding all parts(the structure is ready),the price includes welding rectangular iron(2*2)cm and 2mm thick a long the tent each 80 cm in the roof to fixing the cover,the price includes also painting all parts by two layer oil paint and painting the rec2*2 by one layer of anti rust with all necessary needed to complete the work , all the work should be done according to the instruction of the site engineer .	No	2			
1.4	Covering the tent (Dim 10.40*4.6 m + the arc in the roof) by using a two-layer covers, one of canvas cover of best quality and the second of plastic cover (450 g/m²) to isolate the water and protect the tent and must be the white color, The price includes all necessary needed of screws and sewing to complete the work (sewing the sides, sewing the roof and fix it on the land by ropes, open hole for door/windows) all the work should be done according to the instruction of the site engineer .	M²	300			
1.5	Supply and install iron wall in the tent (2m high *4.60 m length), by made mesh of rectangular profile 4*4 cm, 2 mm thick, and the structure should be covered with zinc sheet 0.7 mm, the price includes install door with all needed to complete the work (lock, welding, handle, frame, antirust paint and two layer of oil paint, for profiles etc), all the work should be done according to the site engineer instructions.	No	2			
1.6	Supply and install cable double coat 2*6 mm between the bazbar and the tents, the work should be done according to the instruction of the site engineer.	ML	60			
1.7	Supply and install unit of light (light LED-30W with socket) (12 No.) , switch, main circuit breakers 16A using cable 4mm,2.5mm...as needed inside plastic pipe 0.5inch with good fixing for the tent, the price includes all needed to complete this work, all the work should be done according to the instructions of the site engineer.	No	2			
1.8	Provide and install outlet source double,the price includes all needed to complete this work(cables-pipes.....), all the works should be done according to the instructions of the site engineer	Piece	12			
1.9	Remove the old fence (chain link,columns,tie concrete 20*20cm)with 180 high to open the new tent with the old one,the price includes movement the rubble out of the camp to a location identified by the local authority, all the works should be done according to the instructions of the site engineer	ML	14			

Financial Offer: General Maintenance Works in Mahmoodly, Twaihiniyah and Tel Semen Camps - NES

العرض المالي: أعمال الصيانة العامة في مخيمات المحمودلي والطويحينية وتل السمن في شمال شرق سوريا

#	Item Description وصف المادة	Unit الوحدة	QTY الكمية	Photo الصورة	Unit Price (USD) سعر الوحدة بالدولار الامريكي	Total Price (USD) سعر الكلي بالدولار الامريكي
1.10	Fence: Supply & Install chain link Fence (3.0 mm dia) of 1.8m height, the fence should be fixed with columns (2.5")dia. 1.8mm thick and struts every 3m (includes provide & install pipes), for the boundaries. the price includes install all columns in pits 40*40*50 cm with concrete and casting tie for the fence (Dim 20cm width, 20 cm high and for all the Fence) and rectangular iron 5*3 cm 2mm thick in the top,all the work should be done according to the details and site engineer instructions.	ML	44			
1.11	supplying metalic locker to save files Dim 90 cm width,180 high, 40 cm deep from the high quality, all the work should be done according to the site engineer instructions.	No	8			
1.12	Provide wooden table 200*100 cm with iron legs durable reliable of a high quality, all the works should be done according to instructions of the site engineer.	No	2			
1.13	Provide and install high quality LED projector lighting device 50W , 220-240V with all accessories needed to complete the work,all the work should be done according to the site engineer instructions.	No	2			
2 General Maintenance						
2.1	Supply and install pump (0.75Hp) : The price includes provision of automatic bossting system, and connecting it with the main source (elevated water tank) and electric system, according to the site engineer instructions.	No	1			
2.2	Replacement the damaged spot light inside the meeting room with a new spot 18W and white colour,all the works should be done according to the instructions of the site engineer.	No	5			
2.3	Maintenance cover of manhole by construct one row of solid block(15*20*40)cm and leveling and spreading crush stone around the manhole ,all the work should be done according to the details and site engineer instructions.	No	25			
2.4	Provide and install a ceramic toilet seat western type of a high quality ,the price includes install and elbow,taps with all accessories needed to complete this work with a plastic washbasin with accesories needed and the samples should be checked and approved by site engineer before installation, with all necessary need to complete the work, all works should be done according to site engineer instructions.	No	7			
Sub-Total Price USD for section A						
B Maintenance work in Mahmoodly Camp						
1	supply and install iron for Signboard dim 93 * 68 cm used a angle triangle 3*3cm as frame,the price including all needed to complete the work (look, welding, handle, frame,.....etc), all the work should be done according to the instruction of the site engineer.	No	8			
2	Covering the tent (Dim 20*6 m + the arc in the roof) by using a two-layer covers, one of canvas cover of best quality and the second of plastic cover (450 g/m²) to isolate the water and protect the tent and must be the white color, The price includes all necessary needed of screws and sewing to complete the work (sewing the sides, sewing the roof and fix it on the land by ropes, open hole for doorwindows) all the work should be done according to the instruction of the site engineer .	M²	550			
Sub-Total Price USD for section B						

Financial Offer: General Maintenance Works in Mahmoodly, Twaihiniyah and Tel Semen Camps - NES
العرض المالي: أعمال الصيانة العامة في مخيمات المحمودلي والطويحينية وتل السمن في شمال شرق سوريا

#	Item Description وصف المادة	Unit الوحدة	QTY الكمية	Photo الصورة	Unit Price (USD) سعر الوحدة بالدولار الامريكي	Total Price (USD) سعر الكلي بالدولار الامريكي
C Maintenance work in Twaihiniyah Camp						
1	supply all materials to casting tie of concrete(1:2:4) for the fence in community tent space with Dim 20cm width, 20 cm high and for all the Fence, the price includes watering work as well, all the works should be done according to the instructions of the site engineer.	ML	122			
Sub-Total Price USD for section C						
Grand Total Amount in (USD) of Sections A, B and C						

NOTE:

- Our organization is not bound to buy the whole quantity mentioned in the Financial Offer.
- Our organization is not bound to contract with one company and can split the award between one or more companies.
- The Service must be delivered to Mahmoodly, Twaihiniyah and Tel Saman Camps, in North East SYRIA, as per the instruction of Our Organization's Supervisor.
- The offered Price includes, transportation, loading & unloading and any other cost to deliver and Implementation to locations mentioned in point(3) in North East SYRIA
- The company must submit approved site visit form and to be added to bid documents.

ملاحظة:

- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة، ويمكن تجزئة العطاء بين أكثر من شركة.
- يتم تسليم الخدمات المذكورة اعلاه الى مخيمات المحمودلي، طويحينية و تل السمن في شمال شرق سوريا وحسب الخطة المقدمة من قبل مشرف المشروع للمنظمة.
- الأسعار المقدمة يشمل جميع المصاريف من نقل و تحميل و التسليم والتنفيذ للمناطق المذكورة في النقطة رقم (3) اعلاه في شمال شرق سوريا.
- يجب على الشركة تقديم استمارة زيارة الموقع موقعة و معتمدة من قبل المهندس المشرف للمنظمة و يجب ارفاقها مع مستندات العطاء المقدم.

Name of Signatory:.....

Title of Signatory:.....

Name of Bidder:.....

Signature & stamp:

Date of Signing:.....