


Financial Offer: Maintenance and Rehabilitation of Electrical Network in Tel Saman Camp - NES العرض المالي: صيانة وإعادة تأهيل الشبكة الكهربائية في مخيم تل سمان - شمال شرق سوريا							
#	Description of the Items	Qty	Unit	Unit Cost (US\$)	Total Cost (US\$)	Photo	Remarks
1	Provide workers with all tools needed to remove all the old and damaged electrecity network inside the camp included (cables,breakers panels,switches.....)etc,all the works should be done according to the details and site engineer instructions .	1	L.S				
2	Provision and installation metal pole 2,5 meter (8x8) cm thickness 2 mm, with metal plate (40X40)cm thickness 2mm should be welded to the pole with anti rain protection (Sunshade) as drawing attached (Appendix A), With three layers of paint,all the works should be done according to the details and site engineer instructions .	120	NO.				
3	Excavation, Provision and installation concrete base rate cement 250kg/m3 for metal pole bases Dim(40x40x50cm), including backfilling, removal of surplus matrial,all the works should be done according to the details and site engineer instructions .	120	NO.				
4	Provision and installation metal circuit breakers panel with suitable lock and rain cover and painted accomodate to 12 breakers ,the price includes a piece of wood (40x40)cm thickness 14mm which will be fixed between the metal plate and th metal breaker panel, with all accessories to complete the work ,all the works should be done according to the details and site engineer instructions .	120	NO.				The sample is required for the metal panel
5	Provision and installation Electrical circuit breaker- MCB - thermal magnetic operation-40 A - tow pole(1 ph +N) - type C - first quality.with all accessories for installation inside metal panel ,all the works should be done according to the details and site engineer instructions .	120	NO.				The sample is required for the circuit breaker
6	Provision and installation Electrical circuit breaker- MCB - thermal magnetic operation-3A - one pole(single phase) - type C - first quality.with all accessories for installation inside metal panel ,all the work should be done according to the details and site engineer instructions.	801	NO.				The sample is required for the circuit breaker
7	Provision and installation electrical stranded Cable (2x6) mm² Cu/ PVC shield and PVC filling - first quality, with all accessories for installation between the public network and each metal breakers panel,all the works should be done according to the details and site engineer instructions .	2700	M.L				The sample is required for the cable
8	Provision and installation electrical stranded Cable (2x2.5) mm² Cu/ PVC shield and PVC filling -first quality, with all accessories for installation between the metal breakers panel and each tent,The extension is underground to a depth of 15 cm and the cable is placed into a strong plastic pipe 0.5 inch with all the necessary work, accessories, and all excavation and backfilling work,all the works should be done according to the details and site engineer instructions .	8000	M.L				The sample is required for the cable and the plastic pipe
9	Provision and installation full electrical outlet socket, 16 A , 250V ,Next to the tent door with the plastic mounting box (external), mounting plate and cover plate,all the sockets must be of the "Schuko" type.The price includes the cable which should be (2x2.5)mm² Cu/ PVC shield NYA, all cables are fixed to structure of the tent inside plastic pipe.with all needed works, materials and accessories,all the work should be done according to the details and site engineer instructions.	801	NO.				The sample is required for the outlet socket and the plastic pipe
10	Provision and installation LED lamp 9 watts (first quality) with plastic holder,the price includes the cable which should be (2x1.5)mm² Cu/ PVC shield NYA,and connect this lamp to the operating switch, all cables are fixed to structure of the tent inside plastic pipe with all needed works, materials and accessories,all the work should be done according to the details and site engineer instructions.	801	NO.				The sample is required for the lamp,holder,switch,cable(2X1.5) and the plastic pipe
Total cost in USD							

NOTE:

1- Our organization is not bound to buy the whole quantity mentioned in the BOQ.

2- The vendor must provide samples of each highlighted item in Yellow in above table along with his offer to (Derik office in North East Syria), and the samples should meet the organization specification, otherwise his offer will be excluded.

3- Our organization is not bound to contract with one company and can split the award between one or more companies.

4- The Delivery location is Tel Saman camp in North East Syria

ملاحظة:

- 1- منضمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- 2- يجب على المورد تقديم عينة (نموذج) لكل مادة مؤشرة باللون الاصفر اعلاه مع عرضه الى (مكتب ديريك في شمال شرق سوريا)، ويجب أن تفي العينات بمواصفات المنظمة، وإلا سيتم استبعاد عرضه.
- 3- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة, و يمكن تجزئة العطاء بين أكثر من شركة
- 4- موقع التسليم هو مخيم تل سمان في شمال شرق سوريا.

Name of Signatory:_____

Title of Signatory:_____

Name of Bidder:_____

Signature & stamp:

Date of Signing:_____