

Financial Offer: Maintenance of the Communal Kitchens in Al-Hol Camp - NES

العرض المالي: صيانة المطابخ الجماعية في مخيم الهول - شمال شرق سوريا

#	Item Description وصف المادة	QTY الكمية	Unit الوحدة	Unit Price (USD) سعر الوحدة بالدولار الامريكي	Total Price (USD) سعر الكلي بالدولار الامريكي
1	supplying and installing tarpaulin cover and install it over the communal kitchens , as follows: 1- the weight :200 (+ - 10 gram)gram/m². * The fixing should be for the communal kitchens:(10.25*6.10) m²2), tarpaulin cover should be fixed , by fixing rope width 2 cm, according to the instructions of engineer and attached drawings, : it will be install over the canvas if needed (mentioned in item 2) , and both layer (canvas and tarpaulin) will be fixed together, the price includes removing all the exist damaged tarpuline and plastic sheet, all the work should be done according to the site engineer instructions,	3460	M²		
2	supplying and installing canvas cover and install it over the metal frame, as follows: 1- the weight :600 (+ - 20 gram) gram/m². The fixing should be : canvas should be fixed with the block wall from the four sites of the communal kitchens, by fixing rope width 2 cm, the price includes removing all the exist damaged canvas and plastic sheet, and all the work should be done according to the site engineer instructions	3750	M²		
3	supplying and installing canvas cover and install it on the sides of communal kitchens as follows: 1- the weight :600 (+ - 20 gram) gram/m². The fixing should be : canvas should be fixed on the exist steel structure according to the instructions of engineer and attached drawings, the cost includes removing all the exist damaged canvas.	2075	M²		
4	Metal Struhcure works for doors : Providing and installation metal door using external and internal frames from an angle metal 4 cm * 4 cm, thickness 4 mm with horizontal beams 4 cm * 4 cm * 4 mm every 70 cm with metal sheet covering 1 mm thickness with paint and lock and all necessary, all the work should be done according to the site engineer instructions,	221	M²		
5	Rehabilitation of the windows by adding the necessary metal sections (external or internal frames or parts of them) with the providing and implementation of 4 mm thick crystal with the necessary locks, paint and all that is necessary. all the work should be done according to the site engineer instructions,	50	M2		
Total Amount in (USD)					

NOTE:

- Our organization is not bound to buy the whole quantity mentioned in the Financial Offer.
- Our organization is not bound to contract with one company and can split the award between one or more companies.
- The Service must be delivered to Phase 01, Phase 02 and Phase 03 in Al-Hol Camp in North East SYRIA, as per the instruction of Our Organization's Supervisor.
- The offered Price includes, transportation, loading & unloading and any other cost to deliver and Implementation to locations mentioned in point(3) in North East SYRIA
- The company must submit approved site visit form and to be added to bid documents.

ملاحظة:

- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة، و يمكن تجزئة العطاء بين أكثر من شركة.
- يتم تسليم الخدمات المذكورة اعلاه الى القطاع الاول، القطاع الثاني و القطاع الثالث في مخيم الهول في شمال شرق سوريا وحسب الخطة المقدمة من قبل مشرف المشروع للمنظمة .
- الأسعار المقدمة يشمل جميع المصاريف من نقل و تحميل و التسليم والتنفيذ للمناطق المذكورة في النقطة رقم (3) اعلاه في شمال شرق سوريا .
- يجب على الشركة تقديم استمارة زيارة الموقع موقعة و معتمدة من قبل المهندس المشرف للمنظمة و يجب ارفاقها مع مستندات العطاء المقدم.

Name of Signatory:.....

Title of Signatory:.....

Name of Bidder:.....

Signature & stamp:

Date of Signing:.....