

FINANCIAL OFFER: General Maintenance and Rehabilitation in Hassaka Collective Centers in Northeast Syria.

العرض المالي: صيانة عامة وإعادة تأهيل لمراكز الحسكة الجماعية في شمال شرق سوريا

#	Description of the Items	Qty	Unit	Unit Cost (USD)	Total Cost (USD)	Sample Check
1	Repair and maintenance light point by supply and installing saving electric bulb not less than 24 watts with all accessories (plastic tube, switches, heater outlet, frame - cable 2*1.5mm ² ..etc) as per need, best quality in the market. all works should be done according to instructions of the site engineer.	1233	No			
2	Rehabilitation electrical light points and installing (full light point) consist of : re-chargeable bulb not less than 15 watt with all accessories (plastic tube, switches - single 2*1.5mm ² ..etc), the frame and magic box as per need best quality in the market. the works should be done according to instructions of the site engineer.	257	No			
3	Rehabilitation electrical light points and installing (full light point) consist of saving electric bulb not less than 24 watts with all accessories (plastic tube, switches - single 2*1.5mm ² ..etc),the frame and magic box as per need, best quality in the market. all works should be done according to instructions of the site engineer.	241	No			
4	Rehabilitation electrical points by installing electrical point by supply and install full electrical point with all accessories (plastic tube, heater outlet, - single 2*2.5 mm ² ..etc) ,the frame and magic box as per need,best quality in the market. all works should be done according to instructions of the site engineer.	247	No			
5	Repair and replace electric cable by providing and extension electric cable 2*2.5 mm ² with (plastic tube with all necessary- as per needs) best quality in the markets the price including all needs, all works should be done according to instructions of the site engineer .	772	ML			yes
6	Replacing A circuit breaker by providing and installing 32 Amp circuit breaker (best quality) all works should be done according to instructions of the site engineer .	33	No			yes
7	maintaining A circuit breaker by providing and installing 3 Amp circuit breaker (best quality) with single Boxes all works should be done according to instructions of the site engineer.	61	No			yes
8	Providing and installing quadrilateral knife switch100 Amp with all needs best quality in markets, all works should be done according to instructions of the site engineer.	3	No			yes
9	Providing and installing Three-phase breaker with a capacity of 40 Amps with all needs best quality in markets, all works should be done according to instructions of the site engineer.	2	No			
10	Repair and replace electric cable network by providing and extension electric cable 2*4 mm2 with(plastic tube with all necessary, as per needs), best quality in the markets the price including all needs, all works should be done according to instructions of the site engineer.	145	ML			yes
11	Replacing A circuit breaker by providing and installing 20 A circuit breaker (best quality), all works should be done according to instructions of the site engineer .	17	No			
12	Maintenance electric network by collecting and fixing electric cables in suitable rainy plastic tube, the price including Plastic tie straps, all needed works, all works should be done according to instructions of the site engineer.	546	ML			
13	Replacing knife switch by providing and installing knife switch 100 AM with all needs best quality in markets, all works should be done according to instructions of the site engineer .	41	No			
14	Repair and replace electric cable by providing and extension electric cable 2*1.5 mm ² with (plastic tube with all necessary, as per needs) best quality in the markets the price including all needs, all works should be done according to instructions of the site engineer.	442	ML			
15	Replacing circuit breaker by providing and installing 10 Amp circuit breaker (best quality), all works should be done according to instructions of the site engineer.	47	No			
16	Providing and extension rainy electric cable 4*6 mm2/ (nyy) to connect the collective centers and the main electricity network with all necessary needs best quality in the markets the price including needed works, all works should be done according to instructions of the site engineer.	76	ML			
17	Repair and replace the old electrical cable by: Providing and extension rainy electric cable 2*6 mm2/ (nyy) to connect the collective centers and the main electricity network with all necessary needs best quality in the markets the price including needed works, all works should be done according to instructions of the site engineer.	99	ML			
18	Repair and replace electric cable network by providing and extension (single cable) 6 mm with plastic tube and distribution boxes with all necessary as per needs, best quality in the markets the price including all needs and works , all works should be done according to instructions of the site engineer.	868	ML			
19	providing and installing outer plastic electrical panel (watertight) its dimension must be suitable for 9 PCs of single circuit breaker best quality in the markets the price including all needs and works, all works should be done according to instructions of the site engineer	22	No			
20	Providing and installing locks for iron doors with all needs and works that needed to be installing, all works should be done according to instructions of the site engineer.	74	No			
Total Amount (USD)						

NOTES:

- 1- All the items should be approved by our organization's site engineer.
- 2- The contractor should clean the site from all remenant and remaining materials after completing the work to the identified location by Local Administration.
- 3- Our organization is not bound to buy the whole quantity mentioned in the BOQ.
- 4- All the item quantities should be apply INCOTERM 2010 DDP (Delivery Duty Paid) to the mentioned locations.
- 5- Our organization is not bound to contract with one company and can split the award between one or more companies.
- 6-The company must submit approved site visit form and to be added to bid documents.

ملاحظات:

- 1- يجب الموافقة على جميع القدرات من قبل مهندس الموقع للمنظمة.
- 2- يجب على المقاول تنظيف الموقع من جميع المواد المتبقية والمخلفات المتبقية بعد الانتهاء من العمل ونقله إلى الموقع المحدد من قبل الإدارة المحلية.
- 3- منظمتنا ليست ملزمة بشراء الكميات الكاملة المذكورة في جدول الكميات.
- 4- جميع كميات المواد يجب أن يكون (التسليم واجب مدفوعة) إلى المواقع المذكورة.
- 5- المنظمة ليست ملزمة بأن تتعاقد مع شركة واحدة، و يمكن تجزئة العطاء بين أكثر من شركة.
- 6.يجب على الشركة تقديم استمارة زيارة الموقع موقعة ومعتمدة من قبل المهندس المشرف للمنظمة و يجب ارفاقها مع مستندات العطاء المقدم.

Name of Signatory: _____

Title of Signatory: _____

Name of Bidder: _____

Signature & stamp:

Date of Signing: _____