



Annex (B)

BOQ for road graveling of Abo Yafeth / Al-Tinera village , length 550, width 8 m.
Al Muqdadiyah District

#	Description	Unit	Quantity	Unit price (IQD)	Total Item Cost
1	<p>Supplying machinery and equipment, for cutting and leveling works of the natural ground with water spraying and compaction, processing soil instability places with boulders wherever needed, and removing the rubble outside the site and at the place allowed by the municipality, with all that is required to complete the work and according to the directions of the supervising engineer.</p> <p>توريد الآلات والمعدات لأعمال قطع وتسوية الأرض الطبيعية مع الرش بالمياه ودكها ، ومعالجة أماكن عدم استقرار التربة بالصخور أينما دعت الحاجة ، وإزالة الركام خارج الموقع وفي المكان الذي تسمح به البلدية ، بكل ما هو مطلوب. لإنجاز العمل وحسب توجيهات المهندس المشرف</p>	m2	4400		
2	<p>Supplying materials, machinery, equipment, and manpower and spraying the road with a layer of sub-base type B (thickness of 15 cm at least, with spraying and good compacting (95%), laboratory test required, and as directed by the supervising engineer.</p> <p>تجهيز المواد والآلات والمعدات والقوى العاملة ورش الطريق بطبقة السببيس (95%) من النوع بي و بسمك 15 سم على الأقل مع الرش والحد الجيد والفحوصات المخبرية المطلوبة وحسب توجيهات المشرف مهندس</p>	m2	4400		
Total					