

FINANCIAL OFFER 3: General Maintenance in Newroz Camp in Northeast Syria.

العرض المالي 3: صيانة عامة لمخيم نوروز في شمال شرق سوريا

Shelter Section

Part 1- Road Maintenance in Newroz Camp - NES

#	Description of the Items	Unit	Qty	Unit Price (USD)	Total Price (USD)
1	ROAD MAINTENANCE: Road Maintenance: Providing materials and manpower and suitable machines (Grader, Front end loader, Water tanker, and roller machines) for maintenance of the road inside the camp by leveling the road to be flat after watering and compacting the excited soil, and spreading a layer of crushed stone the thickness not less than 10 cm with leveling, watering, compacting, and remove all the rubble and debris out of the camp to a location identified by the local authority, all the works should be done according to the site engineer's instructions.	M2	2760		
Total Cost in (USD) - Part 1					

Part 2- Maintenance the Play Ground in Newroz Camp - NES

#	Description of the Items	Unit	Qty	Unit Price (USD)	Total Price (USD)
1	PLAY GROUND WORKS				
1.1	SITE PREPARATION: Supply materials, tools, hiring manpower to clearing the designated playground area from the rubbers, and debris, and then leveling the site using equivalent machine such as loader and grader, also using level device for the leveling process, the price includes removing all remanent out of the camp site and to the identified location by L.A., with all necessary needs to complete the work according to the site engineer instructions.	M²	2730		
1.2	FINE SAND: Supply materials and spread a layer of fine sand (loam) free from stones and organic materials, using equivalent machine, tools, with average thickness of not less than 7 cm, all the work should be done according to the site engineer instructions.	M²	2730		
2	BRC Fence: Supply & Install Fence				
2.1	SITE PREPARATION: Supply materials, machine, and tools to leveling the path of the fencing works. And remove all debars to the identified location by municipality, All works should be done according to instruction of site instruction.	ML	220		
2.2	Removal of the damaged existing old fence: Providing materials, tools, and suitable machines to removing the exist damaged chain-link fence, and transport to the location determined by the local authority, also the price including fixing the old column to be vertical and ready to fix the BRC frame on it, with all necessary needs to complete the work according to the site engineer instructions.	ML	220		
2.3	BRC FENCE: Supply materials, tools manpower, implementing frame between each pipe (column) with the course inside the frame using angle line 4cmx4cm, and 4mm thick., also welding steel BRC mesh (5X5) cm with thickness, not less than 4mm and high 3 m, and welding metal plate (20 * 20) cm thickness of 5 mm in the center course, all the work should be done according to the details and site engineer instructions. <i>Note: the dimension between the old column is change between 280 cm and 330 cm</i>	ML	220		
2.4	CONCRETE BEAM: casting concrete beam rate 250 kg / m 3 from concrete along the fence with width 20 cm and height 15 cm.	ML	220		
2.5	ANTI-RUST PAINT: painting works: one layer of anti-rust should be painted for all iron work, according to the site engineer instructions.	ML	220		
2.6	Oil PaintOIL PAINT: Two layers of oil paint with painting the old column all the work should be done according to the details and the site engineer instructions.	ML	220		
Total Cost in (USD) - Part 2					

WASH Section

Maintenance Works for WASH Units in Newroz Camp in Northeast Syria

#	Description of the Items	Unit	Qty	Unit Price (USD)	Total Price (USD)
1	Toilet Caravan				
1.1	Aluminum Door Handle: Maintainance the broken and damaged handles by Remove all old broken door handles and installing new Aluminum handles, "the core and the body of the handle should be made of High-Grade Aluminium Material" without a key/lock base, Finish Powder Coated and the Size 2x4x3 inch, best quality in the local market with all necessary needs to complete the work according to the site engineer's instructions	NO	65		
1.2	Doors: Providing and fixing aluminum work for doors fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions at the top, bottom, and sides with required rubber/ neoprene gasket, etc., also Aluminum sections shall be smooth, rust-free, straight, mitered and jointed mechanically wherever required including cleat angle, stainless steel screws, door hinges, and latches, all complete as per site engineer instructions.	NO	22		
1.3	Doors maintenance work: Provide and install Fiber sheet for internal aluminum doors in necessary places including necessary filling up the gaps at junctions at the top, bottom, and sides with required rubber/ neoprene gasket, etc. according to the site engineer's instructions.	M²	30		

#	Description of the Items	Unit	Qty	Unit Price (USD)	Total Price (USD)
1.4	Aluminum Door hinges: Remove all old broken door hinges and install new hinges in extruded aluminum, Pin, screws, plates in stainless steel, Platelets in galvanized zamak, and Black nylon bushings best quality in the local market with all necessary accessories all the work is to be done according to the site engineer's instructions	Pcs	25		
WASH Section Total Cost in (USD)					
Grand Total in (USD) (Shelter Section + WASH Section)					

NOTES:

- 1- All the items should be approved by our organization's site engineer.
- 2- The contractor should clean the site from all remenant and remaining materials after completing the work to the identified location by Local Administration.
- 3- Our organization is not bound to buy the whole quantity mentioned in the BOQ.
- 4- All the item quantities should be apply INCOTERM 2010 DDP (Delivery Duty Paid) to the mentioned locations.
- 5- Our organization is not bound to contract with one company and can split the award between one or more companies.
- 6-The company must submit approved site visit form and to be added to bid documents.

ملاحظات:

- 1- يجب الموافقة على جميع الفقرات من قبل مهندس الموقع لمنظمتنا.
- 2- يجب على المقاول تنظيف الموقع من جميع المواد المتبقية والمخلفات المتبقية بعد الانتهاء من العمل ونقله إلى الموقع المحدد من قبل الإدارة المحلية.
- 3- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- 4- جميع كميات المواد يجب ان يكون (التسليم واجب مدفوعة) إلى المواقع المذكورة.
- 5- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة. و يمكن تجزئة العطاء بين أكثر من شركة
6. يجب على الشركة تقديم استمارة زيارة الموقع موقعة ومعتمدة من قبل المهندس المشرف للمنظمة و يجب ارفاقها مع مستندات العطاء المقدم.

Name of Signatory: _____

Title of Signatory: _____

Name of Bidder: _____

Signature & stamp:

Date of Signing: _____