

FINANCIAL OFFER 5: General Maintenance in Tapqa Collective Center in Northeast Syria.

العرض المالي 5: صيانة عامة لمراكز الطبقة الجماعية في شمال شرق سوريا

WASH Section					
#	Item description	Unit	Qty	Unit Price (USD)	Total Price (USD)
1	supply materials tools, and remove the damaged pipes and maintenance of the sewage line by providing and install of PVC pipes(10 inch-of high quality) and to be connected between the chambers of sewage system with the main sewage network, the price includes all necessary fittings elbows, and the price includes excavations and backfilling works the backfilling to be by casting concrete for the path over the pipes in the walkways, and for the natural ground to be with natural soil with all necessary needs to complete the work according to the site engineer instructions.	ML	170		
2	Maintenance of sewage system by supply and provide a technical staff with all materials needed to install of PVC pipes(4 inch-of high quality) and to be connected the rooms with the sewage chamber , the price includes all necessary fittings elbows, and the price includes excavations and backfilling works the backfilling to be by casting concrete for the path over the pipes in the walkways, and for the natural ground to be with natural soil Works include installing pipes on walls with metal brackets every 2m. with all necessary needs to complete the work according to the site engineer instructions.	ML	1180		
3	Maintaining and enhance the sewage system by implementing manholes (80X80 cm) internal dimension, with wall thickness 20 cm, Supply tools, machines, laborers and materials and excavations in all type of soil including rocky layers, with variable depth according to the ground level, implementing manholes with walls and base (20cm thickness), casted by reinforced concrete and reinforcement of 1 layers of 12mm dia. and 15cm c/c in both direction , all the works should be done according to the instructions of the site engineer.	NO	9		
4	Manhole covering: casting concrete slab (120X120)cm 10cm thick to be reinforced with 1 layer of bar 6mm Dia. and spacing 15 cm c/c, and making handels for the manhole cover using steel par 12 mm, all the works should be done according to the instructions of the site engineer.	NO	10		
5	Maintaining the damaged and lost doors location by provide and install iron doors size (1.8 - 2.15) m high and (0.7 - 1) m width, by using rectangular profile 4*4cm 2mm thick and angle-line not less 5*5cm 2mm thick and covering with Plate sheet, 2 mm with all painting works anti-rust and oil painting and all accessories needed to complete this work(lock, hinge, handles etc.), fixing the wall over and around door frame with plastering works and all the works should be done according to instructions of site engineer.	M2	4		
6	Maintenance of the sewage network and re-opining the closed pipes and manholes by supplying tools, equipment and workers to remove and clean the drainage network, The work involves pumping water using the water pressure tank to open and remove the solid materials which is stuck within the network and clean all sewage manholes and provide all necessary needs to complete the work according to the site engineer instructions.	LS	5		
7	Providing and installing of water pump 0.75 HP, Q. max 5 - 60 l/min, H max 45 m, 220 - 240 V, 50 Hz, with all necessary needs and connections to complete the work according to the site engineer instructions.	Pcs	4		
8	Maintaining of the Stainless steel siphon floor drainage by Providing and installing of Stainless steel siphon floor drainage (4) inch , this work includes: - excavation, connection, and accessories installation (gully, fitting and elbow) to the sewage line , Fixing the siphon with cement, and back filling works the backfilling to be by casting concrete for the path over the pipes with all necessary needs to complete the work according to the site engineer instructions.	Pcs	10		
9	Western toilet seat: Providing and installing an western toilet seat with all necessary accessories and connections to make the work completed in all details according to instructions from supervising engineer.	No	1		
Total Cost (USD)					
Shelter Section					
#	Item description	Unit	Qty	Unit Price (USD)	Total Price (USD)
1	Site preparation:- Removal of debris, grading, cleaning and clearing the site, and supply suitable machine with labore to leveling site, by using equivalent machines, all outputs are transferred to official landfills designated by the local authorities, with all necessary needs to complete the work, all the work should be done according to the site engineer instructions.	m2	650		
2	Site preparation:- Removal of debris, grading, cleaning and clearing the site, and supply suitable machine with labore to leveling site, by using equivalent machines, the price includes laying crushed stone best type with (10) cm thick at least, the price including watering and compacting the crushed stone, with all necessary needs to complete the work, all the work should be done according to the site engineer instructions.	m3	264		
3	Maintaining the windows by install protection frame :With Dimension (1.2 X 1.4) m for the rooms, the work includes : - for the frame use metal angle-line not less (4x4x0.4) - installing welding metal bars not less (2.5*2.5) cm, every 12 cm - painting works with one layer of anti-rust paint and two layers of oil paint with all necessary needs to complete the work according to the site engineer instructions.	M2	65		
4	Maintaining and rehabilitate the damaged part of the walls and missed part of the walls by supply materials and implement concrete block works using hollow blocks 20*15*40 cm, cement mortar with mixture ratio (1:3), for filling the joints between the concrete block with all necessary needs to complete the work according to site engineer instructions.	M3	67		
5	Provide and rent all equipment, tools and workers to remove all random walls and unstable walls that can collapse and carry all removal products outside the center to the landfills specified by the local authority	M3	22		
6	Maintaining the damaged and lost doors location by provide and install iron doors size (1.8 - 2.15) m high and (0.7 - 1.05) m width, by using rectangular profile 4*4cm 2mm thick and angle-line not less 5*5cm 2mm thick and covering with Plate sheet, 2 mm with all painting works anti-rust and oil painting and all accessories needed to complete this work(lock, hinge, handles etc.), fixing the wall over and around door frame with plastering works and all the works should be done according to instructions of site engineer.	M2	101		
7	provide and install Metal window with : Providing and installing new metal windows , for the rooms ,the work includes : - installing metal angles not less (3x3x0.4)cm , hinges, handles and pad lock - for the frame use metal angles not less (4x4x0.4) - install White polycarbonate plastic panels , and fix by silicone. - paint by (base + oil) with all necessary needs to complete the work according to the site engineer instructions.	M2	14		
Total Cost (USD)					
Grand Total for WASH and Sheler (USD)					

NOTES:

- 1- All the items should be approved by our organization's site engineer.
- 2- The contractor should clean the site from all remenant and remaining materials after completing the work to the identified location by Local Administration.
- 3- Our organization is not bound to buy the whole quantity mentioned in the BOQ.
- 4- All the item quantities should be apply INCOTERM 2010 DDP (Delivery Duty Paid) to the mentioned locations.
- 5- Our organization is not bound to contract with one company and can split the award between one or more companies.
- 6-The company must submit approved site visit form and to be added to bid documents.

ملاحظات:

- 1- يجب الموافقة على جميع الفقرات من قبل مهندس الموقع لمنظمتنا.
- 2- يجب على المقاول تنظيف الموقع من جميع المواد المتبقية والمخلفات المتبقية بعد الانتهاء من العمل ونقله إلى الموقع المحدد من قبل الإدارة المحلية.
- 3- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- 4- جميع كميات المواد يجب ان يكون التسليم واجب مدفوعة إلى المواقع المذكورة.
- 5- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة. و يمكن توزيعه العطاء بين أكثر من شركة
- 6 يجب على الشركة تقديم استمارة زيارة الموقع موقعة ومعتمدة من قبل المهندس المشرف للمنظمة و يجب ارفاقها مع مستندات العطاء المقدم.

Name of Signatory: _____

Title of Signatory: _____

Name of Bidder: _____

Signature & stamp:

Date of Signing: _____