

1

10

1

1

[illegible]

1

Site

1





15	Installation of western toilet base ثبيت زوالت الغربي	Supply and install a new Western-style ceramic toilet good quality, ensuring proper alignment, secure connection to the existing sanitation network (pipes, below, connections,...) and a high-quality finish the price included provide galvanized steel water tap in accordance with the required specifications. All work shall be executed as per technical standards and under the supervision and instructions of the supervising engineer.	توريد وتركيب مرخص من اريكس سوليفيكس ذو جودة جيدة ، مع ضمان الجودة الصحيحة ، والربط السليم بشبكة الصرف الصحي القائمة ، وتثبيت سطل على الزوردة ويشمل اسم الزوردة الكامل مع شبكة السطل من نوع تجميعي وكابيت وزوسيلات وذو سطل سطل على قفل السدا ورقلة الوصلات المطوية ، يثبت سطل جديد مع ابرص ورقلة للمصنعي القوية وضحت ابرص ورقلة وتثبيت الميخس الخشبي	1	Pcs			
16	Construction and installation squetting base works تركيب اساس السكيت تركيب السكيت	Provide and install new Eastern ceramic toilet bowls Indian or Turkish good quality or equivalent and plastic flush tanks size 10L with all requirement (water valve, steel pipe). The price includes the supply and installation of a steel bidet faucet with secure wall mounting using a bracket, PVC joint, Galy with everything necessary to complete the work. Ensure proper installation and connection to the new network. Guarantee balance and a good finish that meets the required specifications. All work must be carried out according to the technical specifications and the instructions of the supervising engineer.	توريد وتركيب ابرص ابرص ورقلة سوليفيكس ذو جودة جيدة ، تركي او هندي او ما يعطيلها ذو الجودة وسيلق قلاش معك ، يثبتك لمدة 10 لتر ، او ، مع تثبيت بشكل صحيح ورقلة القوية الجديدة مع جميع الملحقات الضرورية (قفل كروم ، الاكابيب الزوردة) السطر ويشمل تغيير وتركيب سطل نوع تجميعي مع تثبيت الاكابيب بخنجر بواسطة خنجر بشكل محكم وكلي وتثبيت وقلمة وصل او اي شيء حسب الاقتاج ، وسيلق الزوردة (التيه الجديد مع بقول الوصلات المطوية	7	Pcs			
17	Installation of water tap for handwashing and toilet تركيب حنجر اليد	Supplying and installing of 1/2 or 3/4" inch Turkish origin diameter galvanized steel water tap with everything necessary to complete the work well and according to the directives of the supervising engineer.	تجهيز وضعت حنجر ماء سطل تركي ال قطر 1/2 انچ او 3/4 انچ مع كل ما يلزم الاخر الصل بشكل جيد وضعت لوحات الميخس الخشبي	4	Pcs			
18	water pipes connection تثبيت سبيل	Provide all necessary materials and equipment to replace the existing PPR pipe water for all latrine groups supply network connecting the water tank to the toilets and sinks in different length size 1/2" and 3/4" with new PPR pipes Egyptian plastic pipes, Arnel Al Sharif type, reinforced for distributing hot and cold water, including the supply and installation of all required fittings and components. The work includes creating necessary wall openings to extend the new pipes to 9 toilets and 2 sinks and 1 set of concrete handwashing, with precise placement of faucet locations for handwashing. All work shall be executed in accordance with technical specifications work requirements, and the instructions of the supervising engineer.	توفير جميع المواد والوسائل اللازمة لاستبدال شبكة امداد المياه الحالية لجميع المجموعات السكنية التي كان المياه والمرحاض والمطبخ بملف PPR جيدة ، بطول مختلف بحجم 1/2" و 3/4" ، وتكون التيب بلاستيكية مصرية نوع ابرص ابرص سطل ، مع توريد وتركيب جميع الوصلات والمكونات المطلوبة وتركيب سطل نوع تجميعي مع تثبيت الاكابيب بخنجر بواسطة خنجر بشكل محكم وكلي وتثبيت وقلمة وصل او اي شيء حسب الاقتاج ، وسيلق الزوردة (التيه الجديد مع بقول الوصلات المطوية	1	no			
19	Replacing water handwashing تغيير حنجر اليد	Supply materials and equipment to install new hanging handwashing ceramic sink with water mixers, Plastic water hose 2 chrome valves, and 2 steel pipes to connect water mixers to the chrome valves for teachers' and students W.C, the price includes supplying and connection all necessary accessories such as locks, pipes and any necessary excavation work to ensure the handwashing operates efficiently with ensuring the quality and durability of the installation in accordance with technical specifications and the supervising engineer's instructions.	توفير المواد والالات اللازمة لتركيب حنجر يدوي سطل مع خلاط المياه الصل مع 1 خرطوم ماء القفل كروم عدد 2 وتثبيت سطل عدد 2 ادرسة الحنجر بالاقفل في مكان دورات المياه الخمسة المدرسين والمعلمين السطر ويشمل تغيير ورقلة كافة الملحقات الضرورية من القفل وتوصيلات والتثبيت والقفل ذري سطل حنجر ان وضحت من اجل ضمان عمل المسالك بكفاءة على سبيل تثبيت السطل بدقة عالية ورقلة الوصلات القوية وتوضيحات الميخس الخشبي مع ضمان جودة وصيانة التركيب	2	Pcs			
20	Water float طرفة غمر في الماء	Supplying and material to installing of 1/2 or 3/4" inch water float with including all necessary materials, fittings, and accessories to complete the installation inside the water storage tank and according to the directives of the supervising engineer.	تجهيز وضعت طرفة ماء نوع 1/2 انچ مع كل ملحقات وما يلزم ارضيا داخل الخزان الماء بشكل جيد وضعت لوحات الميخس الخشبي	4	Pcs			
21	Replacing water storage tank تغيير حنجر قديم	Provision of materials, manpower and equipment to remove the old water tanks and provide 1000-liter horizontal shape, three-layer HDPE plastic water storage tank designed specifically for household use good quality . Should meet all relevant standards and regulations and include a 5-year warranty, with everything necessary include 1/2 or 3/4" inch water float to complete the work, according to the directives of the supervising engineer.	تجهيز المواد والعدة اللازمة لعملية القيام برفع حنجر الماء القديمة ونسب حنجران مياه بلاستيكي من مادة البولي ايثيلين على الكفة لمدة 1000 لتر القوي ، ولات او ادرسة حنجر معصم حبيسا للاستخدام المنزلي يجب ان يفي بجميع المعايير واللوائح ذات الصلة وتضمن ضمانا لمدة 5 سنوات وضمان طرية من الدائم وضعت اسفل حنجر لوحات الميخس الخشبي	4	Pcs			
22	Wall Soap dispenser حنجر صابون جداري	Supply and install steel soap dispenser, along with everything necessary to fix it to the wall well, according to the directions of the supervising engineer.	تجهيز وضعت حنجر صابون سطل مع كل ما يلزم التثبيت على الجدار بشكل جيد وضعت لوحات الميخس الخشبي	5	Pcs			
23	Ventilation fan مروحة تهوية	Supplying and installing 8-inch ventilation fan Turkish, chain or, for WASH facilities. The work includes connecting the fan to the electricity source with the operating switch and everything necessary to complete the work well and according to the directions of the supervising engineer.	تجهيز وضعت مروحة طرفة هواء قياسية انچ الحنجر تركي او ، او ، يشمل الصل توصيل الزوردة بمصدر الكهرباء مع طرفة التثبيت وكما ما يلزم اكرام الصل بشكل جيد وضعت لوحات الميخس الخشبي	3	Pcs			
24	Supplying and operation new water pump تجهيز مضخة ماء	Replacement and operation of a 1-HP water pump of good origin (Turkish, Western, or equivalent) with all necessary accessories for replacing the old pump and installing the new one. The price includes pouring a concrete base for the pump measuring 40*40*10 cm, with a protective box, along with all electrical and technical connections and installations to ensure the pump operates according to the supervising engineer's approvals.	تثبيت وتغيير مضخة مياه قديمة 1 حصان من اصل جيد تركي ، هندي او ما يعطيلها مع جميع الملحقات اللازمة وتثبيت يشمل التغيير سطل س ي س او ، 3/4 انچ حنجر 40 سم مع 5 كفة حنجر ابرص التوصيل اللازمة ، خرطوم ترينج 10*20 سم اسطوانة 40 سم من مصدر ابرص الى سطل الزوردة داخل الحنجر مع حنجر لادعة حرسية المسددة بمسح 10*40 سم مع حنجر حنجر ، بالاضافة الى كافة التوصيلات الكهربائية والقوية والتجهيزات لضمان تشغيل المضخة ورقلة ابرص الوصلات الخشبي	1	Pcs			

Replacement of Electrical Wiring and Installation of New wire and lighting Points تغيير كبريتية و تركيب لمبات جديدة و ربطه	Supply material and replace the old electrical wire and install, connect, and test a new lighting point with electrical wiring. Use 2x1.5 mm² copper wire (Jordanian-made) for toilet interiors. This includes installing a Plug switch, socket, and fixing the wires to the wall using clips (trench) and screws or Burying plastic burial (All quantities of work are detailed below, listed separately for clarity). All materials and accessories should be of Jordanian high quality or equivalent and must be carried out according to the LED light 32W, Water Proof, Good quality, Saudi or Jordanian Wire (2x1.5 mm²) with clips (trench)	تجهيز مواد و تثبيت اسلاك الكبريتية القديمة مع تركيب جديد و توصيلها و اختبارها مع اسلاك جديدة مع التركيب تجهيز مواد و تثبيت اسلاك الكبريتية القديمة مع تركيب جديد و توصيلها و اختبارها مع اسلاك جديدة مع التركيب تجهيز مواد و تثبيت اسلاك الكبريتية القديمة مع تركيب جديد و توصيلها و اختبارها مع اسلاك جديدة مع التركيب
25 Replacement of Electrical Wiring and Installation of New wire and lighting Points تغيير كبريتية و تركيب لمبات جديدة و ربطه	Plug switch (13-16 AMP) Good quality, Saudi or Jordanian Socket (one, two and three line) (13-16 AMP) Good quality, Saudi or Jordanian 40 A circuit breaker, Good quality, Saudi or Jordanian light Waterproof cover base, oval shape, Saudi or Jordanian LED light 20W, Good quality, Saudi or Jordanian Plastic or steel base of switch plug	8 Pcs 50 ML 3 Pcs 3 Pcs 1 Pcs 6 Pcs 6 Pcs 3 Pcs
26 Rehabilitation the iron water tank holder تجديد حامل الخزانات الحديدية	Preparing the necessary materials to rehabilitate the iron water tank holder includes: 1- Preparing a plywood piece measuring 2'2 meters with a thickness of 2.3 cm, or a Chequered Plates measuring 2'2 meters with a thickness of 2.2-2.5 mm, to be used as the base under the tanks. 2- Removing rust thoroughly from the body of the holder using a wire brush, sandpaper, or sandpaper, with replacement all worn parts if any 3- Painting the body with two coats of anti-rust oil paint, followed by two coats of red or grey oil paint. 4- Securing the ascending and descending water pipes to and from the tanks with suitable clamps and ties to the holder structure to prevent movement at appropriate intervals. 5- Preparing and installing four water valves 1/2" or 3/4" to control the water going up and down at the beginning of the tank (from the top) and at the base of the holder (from the bottom), the price includes a necessary fittings such as unions, elbows, and connectors. All work is subject to the approval of the supervising engineer.	2 Pcs
27 RW visibility تجديد الرؤية	Supply and install a high-quality, weather-resistant Dimension (1.5m x 1m) Alucobond or steel plate with a steel frame (4'4 cm) Painted with two coats of anti-rust paint, And painted with the RW and Donor logos for school rehabilitation. The plate must be coated with a transparent adhesive material that prevents dust and water, and securely fixed using steel bolts, With all work requirement and the instructions of the supervising engineer	1 Pcs
TOTAL COST		

with below quantity and details

**Annex C - Rehabilitation WASH Facilities for Three schools in Thi Qar Governorate - ITB-2026-0005 - Al-Shahid Mohammed
Sadiq Alsadi**



[Handwritten signature in blue ink]

